The Gaekwar's Baroda State Railway (GBSR) was a narrow gauge railway line owned by the princely state of Baroda, which was ruled by the Gaekwar dynasty. The railway track has the distinction of being the first narrow gauge line to be laid in British India, and also the first railway to be owned by any princely state of India. In 1862, Maharaja Khanderao Gaekwad, the Maharaja of Baroda, inaugurated 8 miles (13 km) of a 2 feet 6 inches (762 mm) railway line from Dabhoi to Miyagam.

This was a branch to the Bombay, Baroda, and Central India Railway constructed in a gauge of 2 feet 6 inches, by funds furnished by His Highness, the Gaekwar of Baroda. [7 9]

The existing line of railway on the 2 feett 6 inches gauge between Miyagam (a station on the Bombay, Baroda and Central India Railway) and Dabhoi was originally designed and constructed by Mr A.W. Forde, for His Highness the Gaekwar of Baroda as a light tramway to be worked by bullocks. It was afterwards decided to employ engine power, and three small engines were designed by Mr Forde, and obtained from England, weighing about 6 tons each, with fuel and water loaded. Some carriages and trucks were built in India, and thus equipped, the line was opened to traffic.

The light rails, which weighed only 18 lbs to the yard, were, however, not suited to the weight, and the tyres of the wagons became much grooved. After a short time, moreover, the management of the concern fell into the hands of native officials, who allowed the plant to deteriorate, and the line proved a failure and was closed. The sleepers and a good deal of the woodwork of the bridges were stolen, and some of the rails and fastenings too.

In 1870, a proposal was made, by the consulting engineer for railways, Bombay, to His Highness the Gaekwar to restore the line, and entrust the working to the Bombay, Baroda and Central India Railway Company.

The old rails were sold; the line was re-laid with iron rails, weighing 30 lbs to the yard, on teak sleepers. The bridges were repaired and strengthened, and station buildings, quarters for working staff, etc. were provided on a small scale .

New rolling stock was designed and built by Mr E.B. Carroll, locomotive superintendent, Bombay, Baroda, and Central India Railway, and the three engines were put in order. These were tank engines, cylinders with 8-inch diameters and 16-inch strokes, two pairs of wheels, coupled, 2